


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input checked="" type="checkbox"/>				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Thayer 10-2-4-1W				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WINDY RIDGE				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) FEE			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Farrell and Jolene Farnsworth						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-733-0375				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') PO Box 111, Duchesne, UT 84021						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		1865 FSL 1847 FEL		NWSE	2	4.0 S	1.0 W	U		
Top of Uppermost Producing Zone		1865 FSL 1847 FEL		NWSE	2	4.0 S	1.0 W	U		
At Total Depth		1865 FSL 1847 FEL		NWSE	2	4.0 S	1.0 W	U		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 527			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1320			26. PROPOSED DEPTH MD: 8325 TVD: 8325				
27. ELEVATION - GROUND LEVEL 5037			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	12.25	8.625	0 - 900	24.0	J-55 ST&C	8.3	Class G	365	1.17	15.8
PROD	7.875	5.5	0 - 8325	17.0	N-80 LT&C	9.0	35/65 Poz	295	3.5	11.0
							50/50 Poz	523	1.35	14.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Mandie Crozier				TITLE Regulatory Tech			PHONE 435 646-4825			
SIGNATURE				DATE 01/15/2014			EMAIL mcrozier@newfield.com			
API NUMBER ASSIGNED 43047542520000				APPROVAL  Permit Manager						

Newfield Production Company
Thayer 10-2-4-1W
NW/SE Section 2, T4S, R1W
Uintah County, UT

Drilling Program

1. Formation Tops

Uinta	surface
Green River	2,595'
Wasatch	7,525'
TD	8,325'

2. Depth to Oil, Gas, Water, or Minerals

Green River	2,595' - 7,525'
Wasatch	7,525' - TD

Fresh water may be encountered in the Uinta Formation, but is not expected below about 947'.

3. Pressure Control

Section BOP Description

Surface 12-1/4" diverter bowl

Production The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 3M system.

A 3M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 3,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Couple	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom							Burst	Collapse	Tension
Surface 8 5/8	0'	900'	24	J-55	STC	8.33	8.4	12	2,950	1,370	244,000
									5.84	4.73	11.30
Production 5 1/2	0'	8,325'	17	N-80	LTC	8.8	9	--	7,740	6,290	348,000
									2.60	2.05	2.46

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

Up to 20' of conductor drive pipe may be used, minimum diameter 13 3/8"

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Surface	12 1/4	900'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	427	15%	15.8	1.17
				365			
Production Lead	7 7/8	5,190'	35/65 Poz/Type II + 5% Bentonite	1034	15%	11.0	3.5
				295			
Production Tail	7 7/8	3,135'	50/50 Poz/Type II	706	30%	14.0	1.35
				523			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the production casing string will be calculated from an open hole caliper log, plus 15% excess.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 900'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. A diverter bowl will be used in place of a rotating head. Water will be on location to be used as kill fluid, if necessary.
900' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite. Anticipated maximum mud weight is 9.0 ppg.

7. Logging, Coring, and Testing

Logging:	A dual induction, gamma ray, and caliper log will be run from TD to the base of the surface casing. A compensated neutron/formation density log will be run from TD to the top of the Garden Gulch formation. A Gamma Ray log will be run from TD to surface. A cement bond log will be run from PBTD to the cement top behind the production casing.
Cores:	As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.46 psi/ft gradient.

$$8,325' \times 0.46 \text{ psi/ft} = 3810 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

This is planned as a vertical well.



Newfield requests the following Variances from Onshore Order # 2:

- Variance from Onshore Order 2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

CONFIDENTIAL


Typical 3M BOP Stack Configuration



3M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY
[54 FR 39528, Sept. 27, 1989]

T4S, R1W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**


WELL LOCATION, 10-2-4-1W, LOCATED
AS SHOWN IN THE NW 1/4 SE 1/4 OF
SECTION 2, T4S, R1W, U.S.B.&M. UINTAH
COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**


180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501


DATE SURVEYED: 12-16-13	SURVEYED BY: Q.M.	VERSION:
DATE DRAWN: 12-17-13	DRAWN BY: M.W.	V1
REVISED:	SCALE: 1" = 1000'	

NAD 83 (SURFACE LOCATION)
LATITUDE = 40°09'42.93"
LONGITUDE = 109°57'38.75"
NAD 27 (SURFACE LOCATION)
LATITUDE = 40°09'43.07"
LONGITUDE = 109°57'36.22"

= SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on
an N.G.S. OPUS Correction. LOCATION:
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'





Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

Proposed 10-2-4-1W Pad
Proposed Well: 10-2-4-1W
Sec. 2, T4S, R1W, U.S.B.&M.
Uintah County, UT.


DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	12-19-2013		V1
SCALE:	1:100,000		

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

- Existing Road
- Previously Proposed Road
- Proposed Road

Total Road Distances

Proposed Road ± 1,607'

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

Proposed 10-2-4-1W Pad
Proposed Well: 10-2-4-1W
Sec. 2, T4S, R1W, U.S.B.&M.
Uintah County, UT.


DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	12-19-2013		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

Proposed 10-2-4-1W Pad
Proposed Well: 10-2-4-1W
Sec. 2, T4S, R1W, U.S.B.&M.
Uintah County, UT.

DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	12-19-2013		V1
SCALE:	1" = 2,000'		


TOPOGRAPHIC MAP

SHEET

C

Exhibit "B" Map

Proposed 10-2-4-1W Pad
Proposed Well: 10-2-4-1W

**Legend**

1 Mile Radius



Proposed Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
 F: (435) 781-2518

N

**NEWFIELD EXPLORATION COMPANY**

Proposed 10-2-4-1W Pad
 Proposed Well: 10-2-4-1W
 Sec. 2, T4S, R1W, U.S.B.&M.
 Uintah County, UT.

DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	12-19-2013		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

D

Coordinate Report

[illegible]

P: (435) 781-2501
F: (435) 781-2518

NEWFIELD EXPLORATION COMPANY

**Proposed 10-2-4-1W Pad
Proposed Well: 10-2-4-1W
Sec. 2, T4S, R1W, U.S.B.&M.
Uintah County, UT.**

DRAWN BY:	A.P.C.
DATE:	12-19-2013
VERSION:	V1

REVISÉ:

COORDINATE REPORT

SHEET

1

RECEIVED: January 15, 2014

**AFFIDAVIT OF EASEMENT, RIGHT-OF-WAY AND
SURFACE USE AGREEMENT**

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Thayer 10-2-4-1W well with a surface location to be positioned in the NWSW of Section 2, Township 4 South, Range 1 West, Uintah County, Utah (the "Drillsite Location"). The surface owner of the Drillsite Location is Farrell and Jolene Farnsworth whose address is P.O. Box 111, Duchesne, UT 84021 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement, Right-of-Way and Surface Use Agreement dated December 20, 2013 covering the Drillsite Location and access to the Drillsite Location.

FURTHER AFFIANT SAYETH NOT.



Peter Burns

ACKNOWLEDGEMENT


STATE OF COLORADO §
 §
COUNTY OF DENVER §

Before me, a Notary Public, in and for the State, on this 14th day of January, 2014, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.



NOTARY PUBLIC

My Commission Expires:



**NEWFIELD PRODUCTION COMPANY
THAYER 10-2-4-1W
AT SURFACE: NW/SE SECTION 2, T4S, R1W
UINTAH COUNTY, UTAH**

MULTI-POINT SURFACE USE & OPERATIONS PLAN

The onsite inspection for this pad will need to be set up as soon as the APD is received by the State of Utah DOGM. This will be a new well pad with one proposed vertical well.

1. EXISTING ROADS

- a) To reach Newfield Production Company well location site Thayer 10-2-4-1W, proceed in a southerly direction out of Myton, approximately 3.4 miles to it's junction with an existing road to the east; proceed in a easterly direction approximately 5.9 miles to it's junction with an existing road to the northeast; proceed in a northeasterly direction approximately 0.4 miles to it's junction with the beginning of the proposed access road to the northeast; proceed in a northeasterly direction along the proposed access road approximately 1,607' to the proposed well location.
- b) The proposed location is approximately 10.1 miles southeast of Myton, Utah
- c) Existing native surface roads in the area range from clays to a sandy-clay shale material.
- d) Access roads will be maintained at the standards required by UDOT, Duchesne County or other controlling agencies. This maintenance will consist of some minor grader work for road surfacing and snow removal. Any necessary fill material for repair will be purchased and hauled from private sources.

2. PLANNED ACCESS ROAD

- a) Approximately 1,607 feet of access road trending notheast is planned. The planned access consists of entirely new disturbance across entirely private surface. See attached Topographic Map "B".
- b) The planned access road will consist of a 20-foot permanent running surface crowned and ditched in order to handle any run-off from any precipitation events. The maximum grade will be 10% or less.
- c) Adequate drainage structures, where necessary, would be incorporated into the construction of the access road to prevent soil erosion and accommodate all-weather traffic.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

- a) Refer to Topographic Map "D".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

- a) There are no existing facilities that will be utilized.
- b) It is anticipated that this well will be a producing oil well with some associated natural gas.

- c) Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.
- d) Tank batteries will be built to Federal Gold Book specifications.
- e) All permanent above-ground structures would be painted a flat, non-reflective covert green color, to match the standard environmental colors. All facilities would be painted the designated color at the time of installation (weather permitting). Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.
- f) Newfield Production Company proposes 1,548' of proposed gas pipeline. The proposed pipeline corridor across entirely Fee surface connecting existing pipeline corridor on Fee surface. See attached Topographic Map "C".
- g) Where parallel corridors exist the disturbed area will be 60 feet wide to allow for construction of the proposed access road and pipeline corridor. The pipeline corridor will consist of a 12-inch or smaller natural gas pipeline and a 6-inch or smaller fuel gas line.
- h) The pipeline will tie in to the existing Newfield pipeline infrastructure. The construction phase of the planned access road, proposed pipelines will last approximately (10) days.
- i) The centerline of the proposed route will be staked prior to installation. Pipelines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated.
- j) Lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country, travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of four (4) inches deep, the soil will be deemed too wet to adequately support the equipment.

5. **LOCATION AND TYPE OF WATER SUPPLY**

- a) Newfield Production will transport water by truck from nearest water source. The available water sources are as follows:
 - Johnson Water District (Water Right : 43-7478)
 - Maurice Harvey Pond (Water Right: 47-1358)
 - Neil Moon Pond (Water Right: 43-11787)
 - Newfield Collector Well (Water Right: 47-1817 - A30414DVA, contracted with the Duchesne County Conservancy District).

6. **SOURCE OF CONSTRUCTION MATERIALS**

- a) Construction material for this access road will be borrowed material accumulated during construction of the access road. If any additional borrow or gravel is required, it would be obtained from a local supplier having a permitted source of materials within the general area.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

- a) A small pit (80 feet x 120 feet x 8 feet deep, or less) will be constructed inboard of the pad area. The pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM.
- b) The pit would be lined with 16 mil (minimum) thickness polyethylene nylon reinforced liner material. The liner(s) would overlay straw, dirt and/or bentonite if rock is encountered during excavation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit. A minimum of two feet of free board would be maintained between the maximum fluid level and the top of the pit at all times.
- c) A portable toilet will be provided for human waste.
- d) A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.
- e) After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.
- f) All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Newfield Production Company guarantees that during the drilling and completion of the referenced well, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the referenced well, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

8. **ANCILLARY FACILITIES**

- a) There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

- a) See attached Location Layout Sheet.

Fencing Requirements

- a) All pits will be fenced or have panels installed consistent with the following minimum standards:
 - 1. The wire shall be no more than two (2) inches above the ground. If barbed wire is utilized it will be installed three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.

2. Corner posts shall be centered and/or braced in such a manner to keep tight and upright at all times
 3. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- b) The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. PLANS FOR RESTORATION OF SURFACE:

- a) Producing Location
1. Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.
 2. The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting; the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.
- b) Dry Hole Abandoned Location
1. At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

- a) Farrell and Jolene Farnsworth.

12. OTHER ADDITIONAL INFORMATION

- a) Newfield Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On federal administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- b) A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Location and Reserve Pit Reclamation

Please refer to the Castle Peak and Eight Mile Flat Reclamation and Weed Management Plan.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

Representative

Name: Corie Miller
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #10-2-4-1W, Section 2, Township 4S, Range 1W: Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Nationwide Bond #B001834.



I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

1/14/14
Date

Mandie Crozier
Regulatory Analyst
Newfield Production Company

CONFIDENTIAL

Typical 3M BOP Stack Configuration



3M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY
 [54 FR 39528, Sept. 27, 1989]


NEWFIELD EXPLORATION COMPANY

PROPOSED LOCATION LAYOUT

PROPOSED 10-2-4-1W PAD

PROPOSED WELL: 10-2-4-1W

Pad Location: NWSE Section 2, T4S, R1W, U.S.B.&M.



NOTE:

The topsoil & excess material areas are calculated as being mounds containing 2,490 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.

SURVEYED BY: Q.M.	DATE SURVEYED: 12-16-13	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 12-17-13	V1
SCALE: 1" = 60'	REVISED:	





Tri State

Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 15, 2014

NEWFIELD EXPLORATION COMPANY**CROSS SECTIONS****PROPOSED 10-2-4-1W PAD****PROPOSED WELL: 10-2-4-1W***Pad Location: NWSE Section 2, T4S, R1W, U.S.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1


ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	3,190	3,190	Topsoil is not included in Pad Cut Volume	0
PIT	690	0		690
TOTALS	3,880	3,190	1,580	690

SURVEYED BY: Q.M.	DATE SURVEYED: 12-16-13	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 12-17-13	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078


RECEIVED: January 15, 2014

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****PROPOSED 10-2-4-1W PAD****PROPOSED WELL: 10-2-4-1W***Pad Location: NWSE Section 2, T4S, R1W, U.S.B.&M.*

SURVEYED BY: Q.M.	DATE SURVEYED: 12-16-13	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 12-17-13	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 15, 2014

NEWFIELD EXPLORATION COMPANY***RECLAMATION LAYOUT******PROPOSED 10-2-4-1W PAD******PROPOSED WELL: 10-2-4-1W******Pad Location: NWSE Section 2, T4S, R1W, U.S.B.&M.*****Notes:**

1. Reclaimed Area to Include Seeding of Approved Vegetation and Sufficient Storm Water Management System.
2. Actual Equipment Layout and Reclaimed Pad Surface Area May Change due to Production Requirements or Site Conditions.

DISTURBED AREA:

TOTAL DISTURBED AREA = ±3.28 ACRES
TOTAL RECLAIMED AREA = ±2.75 ACRES
UNRECLAIMED AREA = ±0.53 ACRES


SURVEYED BY: Q.M.	DATE SURVEYED: 12-16-13	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 12-17-13	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 15, 2014

NEWFIELD EXPLORATION COMPANY**PROPOSED SITE FACILITY DIAGRAM****10-2-4-1W PAD****10-2-4-1W EDA-20G0005609**

*Pad Location: NWSE Section 2, T4S, R1W, U.S.B.&M.
 Uintah County, Utah*

**Legend**


Emulsion Line
 Load Rack -----
 Water Line
 Gas Sales
 Oil Line -----

NOT TO SCALE

SURVEYED BY: Q.M.	DATE SURVEYED: 12-16-13	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 12-17-13	V1
SCALE: NONE	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 15, 2014





API Number: 4304754252

Well Name: Thayer 10-2-4-1W

Township: T04.0S Range: R01.0W Section: 02 Meridian: U

Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared: 1/15/2014
Map Produced by Diana Mason



Well Name	NEWFIELD PRODUCTION COMPANY Thayer 10-2-4-1W 4304754252			
String	Surf	PROD		
Casing Size(in)	8.625	5.500		
Setting Depth (TVD)	900	8325		
Previous Shoe Setting Depth (TVD)	0	900		
Max Mud Weight (ppg)	8.3	9.0		
BOPE Proposed (psi)	500	3000		
Casing Internal Yield (psi)	2950	7740		
Operators Max Anticipated Pressure (psi)	3810	8.8		

Calculations	Surf String	8.625	"	
Max BHP (psi)	.052*Setting Depth*MW=	388		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	280	YES	diverter bowl
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	190	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	190	NO	OK
Required Casing/BOPE Test Pressure=		900	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient	

Calculations	PROD String	5.500	"	
Max BHP (psi)	.052*Setting Depth*MW=	3896		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2897	YES	3M BOP, annular preventer and/or dbl rams
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2065	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2263	NO	OK
Required Casing/BOPE Test Pressure=		3000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		900	psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

43047542520000 Thayer 10-2-4-1W

Casing Schematic

8-5/8"
MW 8.4
Frac 19.3

Surface

TOC @
318'

Surface
900 MD

— BMSGW ± 900'

to 0' (25% w/p, tail @ 4929')

TOC @
1620'

— 2595' Green River

5602' tail
5190' ~ Garden Gulch

— 7525' Wasatch

5-1/2"
MW 9.

Production
8325 MD

CONFIDENTIAL

✓ Stop cont.

Well name:	43047542520000 Thayer 10-2-4-1W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Surface	Project ID: 43-047-54252
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 87 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 318 ft

Burst

Max anticipated surface pressure: 792 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 900 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 786 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 8,325 ft
Next mud weight: 9.000 ppg
Next setting BHP: 3,892 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 900 ft
Injection pressure: 900 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	900	8.625	24.00	J-55	ST&C	900	900	7.972	4633
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	393	1370	3.489	900	2950	3.28	18.9	244	12.93 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: March 7, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 900 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43047542520000 Thayer 10-2-4-1W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production	Project ID: 43-047-54252
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 9.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 191 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Burst:

Design factor 1.00

Cement top: Surface

Burst

Max anticipated surface pressure: 2,061 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,892 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Non-directional string.

Tension is based on air weight.
Neutral point: 7,189 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8325	5.5	17.00	N-80	LT&C	8325	8325	4.767	46923

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3892	6290	1.616	3892	7740	1.99	141.5	348	2.46 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: March 17, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8325 ft, a mud weight of 9 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Thayer 10-2-4-1W
API Number 43047542520000 **APD No** 9264 **Field/Unit** WINDY RIDGE
Location: 1/4,1/4 NWSE **Sec 2 Tw 4.0S Rng 1.0W** 1865 FSL 1847 FEL
GPS Coord (UTM) 588500 4446247 **Surface Owner** Farrell and Jolene Farnsworth

Participants

Corie Miller - NFX

Regional/Local Setting & Topography

The location is the Pleasant Valley/ Sand Pass area 8 miles East southeast of Myton. The sand pass facility and numerous ponds are nearby. It is placed just outside of the surface owners cattle pasture under sprinkler just across the Uintah county line. The topography is rather flat with the occasional small butte. This location will be cut out of such feature. Most of the region is wild desert lands but, the local area has a much higher than normal density of wetlands and ponds.

Surface Use Plan

Current Surface Use

Grazing

**New Road
Miles**

Well Pad

Src Const Material

Surface Formation

0.2

Width 260 Length 350

Onsite

UNTA

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;

cultivars for cattle grazing

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits, though none were observed.

Soil Type and Characteristics

light colored clay soil with abundant sands

Erosion Issues Y

roadway into pad and neighboring pads are washed out in many places.

Sedimentation Issues Y**Site Stability Issues Y**

deep windblown sands. Fill will need to be imported for stability

Drainage Diversion Required? N**Berm Required? Y****Erosion Sedimentation Control Required? N**

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit**Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	100 to 200	5
Distance to Surface Water (feet)	300 to 1000	2
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)		0
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		42 1 Sensitivity Level

Characteristics / Requirements

A 40' x 80' x 8' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Operator commonly uses a 16 mil liner with a felt underliner. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. A minimum freeboard of two feet shall be maintained at all times. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

They have agreements the landowner wants to ensure are enforced:
 Dust control (he is required by the county to maintain certain standards. NFX should be held to the same standards)
 disturbance, equipment and vehicles to stay out of areas encompassed by center pivot
 all lines (gas, produced water etc) are to be buried
 The access road built for this pad and the pads we permitted last month are poorly constructed and are impassable. Many culverts are needed. Its already a big mess.
 The pad is placed on deep blow sand. It will need imported gravels for stability

Chris Jensen

2/13/2014

Evaluator

Date / Time

CONFIDENTIAL

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
9264	43047542520000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Farrell and Jolene Farnsworth	
Well Name	Thayer 10-2-4-1W		Unit		
Field	WINDY RIDGE		Type of Work	DRILL	
Location	NWSE 2 4S 1W U 1865 FSL 1847 FEL GPS Coord (UTM) 588505E 4446238N				

Geologic Statement of Basis

Newfield proposes to set 500' of surface casing at this location. The base of the moderately saline water at this location is estimated to be at a depth of 900'. A search of Division of Water Rights records shows 1 water well within a 10,000 foot radius of the center of Section 2. The well is privately owned and located over a mile from the proposed well. Depth is listed as 27 feet. Water use is listed as irrigation and domestic use. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Surface casing should be extended to isolate the base of the moderately saline ground water.

Brad Hill
APD Evaluator

3/6/2014
Date / Time

Surface Statement of Basis

Location is proposed in a good location although outside the spacing window. Access road enters the pad from the West and is currently poorly constructed and impassable. Culverts and other conveyances for overland flows need to be planned and constructed. The landowner and its representative was not in attendance for the pre-site inspection but, was given the chance to express concerns over the phone.

The soil type (deep blow sand) and topography at present do combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions.

Usual construction standards of the Operator do not appear to be adequate for the proposed purpose as submitted.

I recognize no special flora or animal species or cultural resources on site that the proposed action may harm. A riparian area and numerous ponds/ wetlands can be found to the West. The location was not previously surveyed for cultural and paleontological resources (as the operator saw fit). I have advised the operator take all measures necessary to comply with ESA and MBTA and that actions insure no disturbance to species that may have not been seen during onsite visit.

The location should be bermed to prevent fluids from entering or leaving the confines of the pad. Fencing around the reserve pit will be necessary to prevent wildlife and livestock from entering. A synthetic liner of 16 mils (minimum) should be utilized in the reserve pit. Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues. An appropriate type and amount of fill will need to be imported for pad construction

Chris Jensen
Onsite Evaluator

2/13/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
	Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues.
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from entering or leaving the pad. Imported fill must be used to provide stable base for drilling and as a cap for the entire pad
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location and under access roads with culverts.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 1/15/2014

API NO. ASSIGNED: 43047542520000

WELL NAME: Thayer 10-2-4-1W

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: NWSE 02 040S 010W

Permit Tech Review: ☒

SURFACE: 1865 FSL 1847 FEL

Engineering Review: ☒

BOTTOM: 1865 FSL 1847 FEL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.16185

LONGITUDE: -109.96071

UTM SURF EASTINGS: 588505.00

NORTHINGS: 4446238.00

FIELD NAME: WINDY RIDGE

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

- ☒ PLAT
- ☒ Bond: STATE - B001834
- ☐ Potash
- ☐ Oil Shale 190-5
- ☐ Oil Shale 190-3
- ☐ Oil Shale 190-13
- ☒ Water Permit: 437478
- ☐ RDCC Review:
- ☒ Fee Surface Agreement
- ☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

- ☐ R649-2-3.
- Unit:
- ☐ R649-3-2. General
- ☐ R649-3-3. Exception
- ☒ Drilling Unit
- Board Cause No: R649-3-2
- Effective Date:
- Siting:
- ☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 5 - Statement of Basis - bhill
12 - Cement Volume (3) - ddoucet
23 - Spacing - dmason
25 - Surface Casing - hmacdonald

RECEIVED: March 19, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Thayer 10-2-4-1W

API Well Number: 43047542520000

Lease Number: FEE

Surface Owner: FEE (PRIVATE)

Approval Date: 3/19/2014

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-2. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2 production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to surface as indicated in the submitted drilling plan. Tail cement should be brought up above any productive hydrocarbon or flowing water zone.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
 - contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
 - Requests to Change Plans (Form 9) - due prior to implementation
 - Written Notice of Emergency Changes (Form 9) - due within 5 days
 - Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation

- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: Thayer 10-2-4-1W
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1865 FSL 1847 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 02 Township: 04.0S Range: 01.0W Meridian: U		9. API NUMBER: 43047542520000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: WINDY RIDGE
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 17, 2014		
NAME (PLEASE PRINT) Cherei Neilson	PHONE NUMBER 435 646-4883	TITLE Drilling Technician
SIGNATURE N/A	DATE 4/16/2014	

NEWFIELD**Casing****Conductor**

Legal Well Name Thayer 10-2-4-1W		Wellbore Name Original Hole	
API/UWI 43047542520000	Surface Legal Location NWSE 1865 FSL 1847 FEL Sec 2 T4S R1W	Field Name MYTON AREA	Well Type Development
Well RC 500376797	County Uintah	State/Province Utah	Spud Date
		Final Rig Release Date	

Wellbore

Wellbore Name Original Hole	Kick Off Depth (ftKB)
--------------------------------	-----------------------

Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	13	31	4/8/2014	4/8/2014

Wellhead

Type	Install Date	Service	Comment
------	--------------	---------	---------

Wellhead Components

Des	Make	Model	SN	WP Top (psi)

Casing

Casing Description Conductor	Set Depth (ftKB) 31	Run Date 4/8/2014	Set Tension (kips)
---------------------------------	------------------------	----------------------	--------------------

Centralizers	Scratchers
--------------	------------

Casing Components

Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft-lb)	Class	Max OD (in)
Conductor	14	13.500	35.75	H-40		1	18.00	13.0	31.0			

Jewelry Details**External Casing Packer**

Type	Setting Requirement	Release Requirements	Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)
		ECP Load (1000lbf)	Seal Load (1000lbf)		

Slotted Liner

% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)
Slot Description	Slot Pattern	Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)	

Liner Hanger

Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)	Polish Bore Length (ft)
--------------	----------------	---------------------------	-----------------------	-------------------------

Slip Description	Set Mechanics
------------------	---------------

Setting Procedure

Unsetting Procedure

NEWFIELD

Casing

Surface

Legal Well Name Thayer 10-2-4-1W		Wellbore Name Original Hole			
API/UWI 43047542520000	Surface Legal Location NWSE 1865 FSL 1847 FEL Sec 2 T4S R1W		Field Name MYTON AREA	Well Type Development	Well Configuration Type Vertical
Well RC 500376797	County Uintah	State/Province Utah	Spud Date	Final Rig Release Date	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	13	31	4/8/2014	4/8/2014
Vertical	12 1/4	31	493	4/8/2014	4/8/2014
Vertical	12 1/4	493	943	4/9/2014	4/9/2014

Wellhead			
Type	Install Date	Service	Comment

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description Surface	Set Depth (ftKB) 935	Run Date 4/9/2014	Set Tension (kips)
Centralizers 3	Scratchers		

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)
Wellhead	8 5/8	8.097	24.00	J-55	ST&C	1	2.00	13.0	15.0			
Cut Off	8 5/8	8.097	24.00	J-55	ST&C	0	0.00	15.0	15.0			
Cut off	8 5/8	8.097	24.00	J-55	ST&C	1	41.50	15.0	56.5			
Casing Joints	8 5/8	8.097	24.00	J-55	ST&C	19	832.25	56.5	888.7			
Float Collar	8 5/8	8.097	24.00	J-55	ST&C	1	0.92	888.7	889.6			
Shoe Joint	8 5/8	8.097	24.00	J-55	ST&C	1	43.95	889.6	933.6			
Guide Shoe	8 5/8	8.097	24.00	J-55	ST&C	1	1.42	933.6	935.0			

Jewelry Details							
External Casing Packer							
Type	Setting Requirement	Release Requirements	Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)		
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)	Seal Load (1000lbf)

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern	Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)		

Liner Hanger					
Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)	Polish Bore Length (ft)	
Slip Description	Set Mechanics				
Setting Procedure					
Unsetting Procedure					

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pro Petro 8
Submitted By Branden Arnold Phone Number 4354010223
Well Name/Number Thayer 10-2-4-1W
Qtr/Qtr NWSE Section 2 Township 4S Range 1W
Lease Serial Number FEE
API Number 43-04754252

CONFIDENTIAL

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 4/8/2014 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 3:00 4/8/2014 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: Thayer 10-2-4-1W
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1865 FSL 1847 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 02 Township: 04.0S Range: 01.0W Meridian: U		9. API NUMBER: 43047542520000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: WINDY RIDGE
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 4/8/2014 <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 4/8/14 Drill & set 18' of 14" conductor. Drill f/18' to 480' KB of 12 1/14 hole. On 4/9/14 drill f/480' to 943'KB. P/U and run 21 joints of 24# J-55 8 5/8" casing set depth 935'KB. On 4/10/14 Cement w/Halliburton w/465 sx of 15.8# 1.19 yield class G Neat cement. Returned 19 bbls back to pit & bumped plug to 810 psi.		
NAME (PLEASE PRINT) Cherei Neilson		PHONE NUMBER 435 646-4883
SIGNATURE N/A		TITLE Drilling Technician
DATE 5/1/2014		<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 01, 2014 </div>

NEWFIELD**Casing****Conductor**

Legal Well Name Thayer 10-2-4-1W		Wellbore Name Original Hole			
API/UWI 43047542520000	Surface Legal Location NWSE 1865 FSL 1847 FEL Sec 2 T4S R1W		Field Name MYTON AREA	Well Type Development	Well Configuration Type Vertical
Well RC 500376797	County Uintah	State/Province Utah	Spud Date	Final Rig Release Date	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	13	31	4/8/2014	4/8/2014

Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing				
Casing Description Conductor	Set Depth (ftKB) 31	Run Date 4/8/2014	Set Tension (kips)	
Centralizers	Scratchers			

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft-lb)	Class	Max OD (in)
Conductor	14	13.500	35.75	H-40		1	18.00	13.0	31.0			

Jewelry Details									
External Casing Packer									
Type	Setting Requirement		Release Requirements		Inflation Method	Vol Inflation (gal)		Equiv Hole Sz (in)	
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)		Seal Load (1000lbf)	

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern		Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)	

Liner Hanger					
Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)	Polish Bore Length (ft)	
Slip Description			Set Mechanics		

Setting Procedure					
Unsetting Procedure					

NEWFIELD

Casing

Surface

Legal Well Name Thayer 10-2-4-1W		Wellbore Name Original Hole	
API/UWI 43047542520000	Surface Legal Location NWSE 1865 FSL 1847 FEL Sec 2 T4S R1W	Field Name MYTON AREA	Well Type Development
Well RC 500376797	County Uintah	State/Province Utah	Spud Date
		Final Rig Release Date	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	13	31	4/8/2014	4/8/2014
Vertical	12 1/4	31	493	4/8/2014	4/8/2014
Vertical	12 1/4	493	943	4/9/2014	4/9/2014

Wellhead			
Type	Install Date	Service	Comment

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description Surface	Set Depth (ftKB) 935	Run Date 4/9/2014	Set Tension (kips)
Centralizers 3	Scratchers		

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft-lb)	Class	Max OD (in)
Wellhead	8 5/8	8.097	24.00	J-55	ST&C	1	2.00	13.0	15.0			
Cut Off	8 5/8	8.097	24.00	J-55	ST&C	0	0.00	15.0	15.0			
Cut off	8 5/8	8.097	24.00	J-55	ST&C	1	41.50	15.0	56.5			
Casing Joints	8 5/8	8.097	24.00	J-55	ST&C	19	832.25	56.5	888.7			
Float Collar	8 5/8	8.097	24.00	J-55	ST&C	1	0.92	888.7	889.6			
Shoe Joint	8 5/8	8.097	24.00	J-55	ST&C	1	43.95	889.6	933.6			
Guide Shoe	8 5/8	8.097	24.00	J-55	ST&C	1	1.42	933.6	935.0			

Jewelry Details							
External Casing Packer							
Type	Setting Requirement	Release Requirements	Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)		
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)	Seal Load (1000lbf)

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern	Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)		

Liner Hanger			
Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)
Slip Description	Set Mechanics		
Setting Procedure			
Unsetting Procedure			

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
FEE

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.

8. Lease Name and Well No.
THAYER 10-2-4-1W9. API Well No.
43-047-54252

10. Field and Pool or Exploratory

11. Sec., T., R., M., on Block and
Survey or Area SEC 2 T4S R1W12. County or Parish
UINTAH13. State
UT17. Elevations (DF, RKB, RT, GL)*
5037' GL 5050' KB1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
Other:2. Name of Operator
NEWFIELD PRODUCTION COMPANY3. Address ROUTE #3 BOX 3630
MYTON, UT 840523a. Phone No. (include area code)
Ph:435-646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 1865' FSL 1847' FEL (NW/SE) SEC 2 T4S R1W

At top prod. interval reported below

At total depth 1837' FSL 2026' FEL (NW/SE) SEC 2 T4S R1W

14. Date Spudded
04/08/201415. Date T.D. Reached
04/29/201416. Date Completed 05/15/2014
☐ D & A ☒ Ready to Prod.18. Total Depth: MD 8330'
TVD 8320'19. Plug Back T.D.: MD 8274'
TVD20. Depth Bridge Plug Set: MD
TVD21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24	0'	935'		465 CLASS G			
7-7/8"	5-1/2" SB-80	17	0'	8321'		620 ELASTICEM		0'	
						450 BONDCM			
						100 PREMC			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@5514'	TA@5444'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River	5570'	7585'	5570' - 7585' MD	0.34	76	
B) Wasatch	7701'	8018'	7701' - 8018' MD	0.34	60	
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
5570' - 8018' MD	Frac w/ 36560#s of 100 mesh, 504,480#s of 20/40 white sand, and 25,600#s of RC, in 9,807 bbls of Lightning 17 fluid, in 6 stages

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
5/13/14	5/23/14	24	→	123	55	105			2.5 X 1.75 X 24' RHAC
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers
GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK GARDEN GULCH 2	5262' 5580'
				X MRKR LODC	6033' 6879'
				CASTLE PEAK BASAL CARBONATE	7145' 7474'
				WASATCH	7600'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather Calder Title Regulatory Technician
 Signature Heather Calder Date 06/03/2014

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 2 T4S, R1W
10-2-4-1W
Wellbore #1**

Design: Actual

End of Well Report

29 April, 2014





Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION Project: USGS Myton SW (UT) Site: SECTION 2 T4S, R1W Well: 10-2-4-1W Wellbore: Wellbore #1 Design: Actual		Local Co-ordinate Reference: Well 10-2-4-1W 10-2-4-1W @ 5050.0usft (CAPSTAR 329) 10-2-4-1W @ 5050.0usft (CAPSTAR 329) True Minimum Curvature EDM 5000.1 Single User Db	
Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		System Datum: Mean Sea Level	
Map System: US State Plane 1983 Geo Datum: North American Datum 1983 Map Zone: Utah Central Zone			
Site SECTION 2 T4S, R1W			
Site Position: From: Map Position Uncertainty: 0.0 usft		Northing: 7,232,211.31 usft Easting: 2,069,879.27 usft Slot Radius: 13-3/16" Latitude: 40° 9' 50.991 N Longitude: 109° 57' 47.540 W Grid Convergence: 0.98°	
Well 10-2-4-1W, SHL: 40° 9' 42.930 -109° 57' 38.750			
Well Position +N/-S 0.0 usft +E/-W 0.0 usft Position Uncertainty 0.0 usft		Northing: 7,231,407.49 usft Easting: 2,070,575.58 usft Wellhead Elevation: 5,050.0 usft Latitude: 40° 9' 42.930 N Longitude: 109° 57' 38.750 W Ground Level: 5,037.0 usft	
Wellbore Wellbore #1			
Magnetics Model Name Sample Date		Declination (°) Dip Angle (°) Field Strength (nT)	
IGRF2010		4/11/2014 10.93 65.84 52,073	
Design Actual			
Audit Notes: 1.0		Phase: ACTUAL Tie On Depth: 0.0	
Vertical Section:		Depth From (TVD) (usft) +N/-S (usft) +E/-W (usft) Direction (°)	
0.0		0.0 0.0 261.01	
Survey Program Date 4/29/2014			
From (usft) To (usft) Survey (Wellbore)		Tool Name Description	
946.0 8,330.0 Survey #1 (Wellbore #1)		MWD MWD - Standard	



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well 10-2-4-1W
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
	946.0	0.30	180.40	946.0	0.4	-2.5	0.0	0.03	0.03	0.00
	989.0	0.20	136.20	989.0	0.4	-2.6	0.0	0.49	-0.23	-102.79
	1,032.0	0.30	215.90	1,032.0	0.4	-2.8	0.0	0.77	0.23	185.35
	1,076.0	0.00	198.00	1,076.0	0.5	-2.9	0.0	0.68	-0.68	0.00
	1,120.0	0.50	318.80	1,120.0	0.6	-2.7	-0.2	1.14	1.14	0.00
	1,163.0	1.10	312.40	1,163.0	1.0	-2.3	-0.6	1.41	1.40	-14.88
	1,207.0	1.80	314.50	1,207.0	1.6	-1.5	-1.4	1.60	1.59	4.77
	1,251.0	2.30	309.80	1,250.9	2.6	-0.5	-2.6	1.20	1.14	-10.68
	1,294.0	2.70	311.30	1,293.9	3.8	0.7	-4.0	0.94	0.93	3.49
	1,338.0	3.30	312.50	1,337.8	5.3	2.3	-5.7	1.37	1.36	2.73
	1,381.0	3.30	312.10	1,380.8	6.8	3.9	-7.5	0.05	0.00	-0.93
	1,424.0	3.50	310.80	1,423.7	8.5	5.6	-9.5	0.50	0.47	-3.02
	1,467.0	3.50	314.10	1,466.6	10.1	7.4	-11.4	0.47	0.00	7.67
	1,511.0	3.40	311.70	1,510.5	11.7	9.2	-13.3	0.40	-0.23	-5.45
	1,554.0	3.40	311.50	1,553.5	13.4	10.9	-15.2	0.03	0.00	-0.47
	1,598.0	3.50	313.80	1,597.4	15.0	12.7	-17.2	0.39	0.23	5.23
	1,642.0	3.60	313.80	1,641.3	16.6	14.6	-19.2	0.23	0.23	0.00
	1,686.0	3.70	315.00	1,685.2	18.3	16.5	-21.2	0.29	0.23	2.73
	1,730.0	3.60	312.70	1,729.1	20.0	18.5	-23.2	0.40	-0.23	-5.23
	1,773.0	3.70	315.20	1,772.0	21.7	20.4	-25.1	0.44	0.23	5.81
	1,817.0	3.60	313.60	1,815.9	23.3	22.3	-27.1	0.32	-0.23	-3.64
	1,861.0	3.60	315.10	1,859.9	25.0	24.3	-29.1	0.21	0.00	3.41
	1,905.0	3.70	312.60	1,903.8	26.7	26.2	-31.1	0.43	0.23	-5.68
	1,948.0	3.60	313.30	1,946.7	28.3	28.1	-33.1	0.25	-0.23	1.63
	1,991.0	3.70	316.90	1,989.6	30.0	30.0	-35.1	0.58	0.23	8.37
	2,035.0	3.40	315.90	2,033.5	31.5	32.0	-37.0	0.70	-0.68	-2.27



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well 10-2-4-1W
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	2,079.0	3.40	316.70	2,077.4	33.0	33.9	-38.8	0.11	0.00	1.82
	2,123.0	3.60	316.50	2,121.3	34.5	35.8	-40.6	0.46	0.45	-0.45
	2,165.0	3.70	321.10	2,163.3	35.9	37.8	-42.4	0.74	0.24	10.95
	2,208.0	3.70	321.80	2,206.2	37.3	40.0	-44.1	0.11	0.00	1.63
	2,251.0	3.90	319.10	2,249.1	38.7	42.2	-45.9	0.62	0.47	-6.28
	2,294.0	3.70	318.30	2,292.0	40.3	44.3	-47.8	0.48	-0.47	-1.86
	2,338.0	3.50	315.30	2,335.9	41.8	46.3	-49.7	0.62	-0.45	-6.82
	2,381.0	3.70	316.00	2,378.8	43.4	48.3	-51.6	0.48	0.47	1.63
	2,425.0	3.70	316.20	2,422.7	45.0	50.3	-53.5	0.03	0.00	0.45
	2,469.0	3.50	317.20	2,466.6	46.6	52.3	-55.4	0.48	-0.45	2.27
	2,512.0	3.60	318.10	2,509.6	48.0	54.3	-57.2	0.27	0.23	2.09
	2,556.0	3.60	317.10	2,553.5	49.5	56.3	-59.1	0.14	0.00	-2.27
	2,600.0	3.60	317.60	2,597.4	51.1	58.4	-61.0	0.07	0.00	1.14
	2,644.0	3.50	314.50	2,641.3	52.6	60.3	-62.8	0.49	-0.23	-7.05
	2,688.0	3.50	312.00	2,685.2	54.3	62.2	-64.8	0.35	0.00	-5.68
	2,732.0	3.30	310.70	2,729.1	55.9	63.9	-66.8	0.49	-0.45	-2.95
	2,774.0	3.40	310.20	2,771.1	57.5	65.5	-68.6	0.25	0.24	-1.19
	2,818.0	3.20	312.80	2,815.0	59.2	67.2	-70.5	0.57	-0.45	5.91
	2,862.0	2.70	311.30	2,858.9	60.6	68.7	-72.2	1.15	-1.14	-3.41
	2,906.0	2.80	306.80	2,902.9	62.0	70.0	-73.8	0.54	0.23	-10.23
	2,949.0	2.40	303.00	2,945.8	63.4	71.1	-75.4	1.01	-0.93	-8.84
	2,993.0	2.20	293.50	2,989.8	64.8	72.0	-77.0	0.98	-0.45	-21.59
	3,037.0	2.00	275.30	3,033.8	66.2	72.4	-78.5	1.57	-0.45	-41.36
	3,080.0	2.10	270.10	3,076.7	67.7	72.4	-80.1	0.49	0.23	-12.09
	3,124.0	2.30	274.00	3,120.7	69.4	72.5	-81.7	0.57	0.45	8.86
	3,168.0	2.70	291.70	3,164.7	71.2	73.0	-83.6	1.97	0.91	40.23
	3,211.0	3.70	296.80	3,207.6	73.2	74.0	-85.8	2.42	2.33	11.86



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION		Local Co-ordinate Reference:							
Project: USGS Myton SW (UT)		10-2-4-1W @ 5050.0usft (CAPSTAR 329)							
Site: SECTION 2 T4S, R1W		10-2-4-1W @ 5050.0usft (CAPSTAR 329)							
Well: 10-2-4-1W		True							
Wellbore: Wellbore #1		Minimum Curvature							
Design: Actual		EDM 5000.1 Single User Db							
Survey									
MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
3,255.0	4.00	301.80	3,251.5	75.5	75.4	-88.3	1.02	0.68	11.36
3,298.0	3.90	295.80	3,294.4	77.8	76.8	-90.9	0.99	-0.23	-13.95
3,342.0	3.30	290.60	3,338.3	80.1	77.9	-93.5	1.55	-1.36	-11.82
3,386.0	3.30	295.70	3,382.2	82.3	78.9	-95.8	0.67	0.00	11.59
3,428.0	3.50	304.10	3,424.2	84.2	80.2	-97.9	1.28	0.48	20.00
3,472.0	3.50	310.50	3,468.1	86.1	81.8	-100.1	0.89	0.00	14.55
3,515.0	3.90	315.00	3,511.0	87.8	83.7	-102.1	1.15	0.93	10.47
3,559.0	3.70	313.80	3,554.9	89.5	85.7	-104.2	0.49	-0.45	-2.73
3,602.0	3.60	311.90	3,597.8	91.2	87.6	-106.2	0.36	-0.23	-4.42
3,646.0	3.60	304.40	3,641.7	93.1	89.3	-108.4	1.07	0.00	-17.05
3,690.0	3.30	311.80	3,685.6	94.9	90.9	-110.4	1.22	-0.68	16.82
3,734.0	3.20	311.30	3,729.6	96.5	92.6	-112.3	0.24	-0.23	-1.14
3,778.0	3.00	299.40	3,773.5	98.2	93.9	-114.2	1.53	-0.45	-27.05
3,820.0	2.80	291.50	3,815.5	99.9	94.9	-116.1	1.06	-0.48	-18.81
3,863.0	2.70	282.90	3,858.4	101.7	95.5	-118.1	0.99	-0.23	-20.00
3,907.0	2.40	279.00	3,902.4	103.6	95.8	-120.0	0.79	-0.68	-8.86
3,951.0	3.20	279.10	3,946.3	105.6	96.2	-122.2	1.82	1.82	0.23
4,125.0	7.50	280.80	4,119.5	120.9	99.1	-138.1	2.47	2.47	0.98
4,169.0	7.20	277.20	4,163.2	126.3	100.0	-143.7	1.25	-0.68	-8.18
4,212.0	6.90	271.50	4,205.8	131.4	100.4	-148.9	1.77	-0.70	-13.26
4,256.0	6.10	262.30	4,249.5	136.3	100.1	-153.9	2.98	-1.82	-20.91
4,299.0	5.90	257.40	4,292.3	140.8	99.3	-158.3	1.28	-0.47	-11.40
4,341.0	6.10	254.20	4,334.1	145.2	98.3	-162.6	0.93	0.48	-7.62
4,384.0	5.50	249.10	4,376.9	149.5	96.9	-166.7	1.84	-1.40	-11.86
4,428.0	4.90	242.30	4,420.7	153.3	95.3	-170.3	1.95	-1.36	-15.45
4,472.0	4.40	235.90	4,464.5	156.6	93.4	-173.4	1.64	-1.14	-14.55
4,515.0	3.60	227.40	4,507.4	159.3	91.6	-175.7	2.31	-1.86	-19.77



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well 10-2-4-1W
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
Survey Calculation Method: True
Database: Minimum Curvature
 EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	4,559.0	3.00	227.80	4,551.4	161.4	89.9	-177.6	1.36	-1.36	0.91
	4,603.0	2.00	226.80	4,595.3	163.0	88.6	-179.0	2.27	-2.27	-2.27
	4,645.0	1.80	221.20	4,637.3	164.1	87.6	-180.0	0.65	-0.48	-13.33
	4,689.0	1.50	206.30	4,681.3	164.9	86.6	-180.7	1.18	-0.68	-33.86
	4,733.0	1.80	192.80	4,725.3	165.5	85.4	-181.1	1.11	0.68	-30.68
	4,777.0	1.60	191.90	4,769.2	166.0	84.1	-181.4	0.46	-0.45	-2.05
	4,819.0	2.00	194.20	4,811.2	166.5	82.8	-181.7	0.97	0.95	5.48
	4,863.0	2.00	184.20	4,855.2	167.0	81.3	-181.9	0.79	0.00	-22.73
	4,907.0	2.30	185.80	4,899.2	167.4	79.7	-182.1	0.70	0.68	3.64
	4,951.0	1.50	186.30	4,943.1	167.9	78.2	-182.3	1.98	-1.82	23.86
	4,994.0	1.50	227.70	4,986.1	168.6	77.3	-182.9	1.89	0.00	73.02
	5,038.0	1.90	216.70	5,030.1	169.6	76.3	-183.8	1.17	0.91	-25.00
	5,081.0	1.90	211.10	5,073.1	170.5	75.2	-184.6	0.43	0.00	-13.02
	5,124.0	2.00	210.70	5,116.1	171.5	73.9	-185.3	0.23	0.23	-0.93
	5,166.0	2.00	209.70	5,158.0	172.4	72.6	-186.0	0.08	0.00	-2.38
	5,210.0	2.10	199.70	5,202.0	173.3	71.2	-186.7	0.84	0.23	-22.73
	5,253.0	1.90	203.90	5,245.0	174.0	69.8	-187.3	0.58	-0.47	9.77
	5,297.0	2.00	191.50	5,288.9	174.7	68.4	-187.7	0.98	0.23	-28.18
	5,340.0	2.20	191.50	5,331.9	175.3	66.9	-188.0	0.47	0.47	0.00
	5,384.0	2.50	191.70	5,375.9	175.9	65.1	-188.4	0.68	0.68	0.45
	5,427.0	2.30	200.40	5,418.8	176.6	63.4	-188.9	0.97	-0.47	20.23
	5,471.0	1.50	199.30	5,462.8	177.4	62.0	-189.4	1.82	-1.82	-2.50
	5,514.0	1.10	206.90	5,505.8	177.9	61.1	-189.7	1.01	-0.93	17.67
	5,558.0	1.30	191.10	5,549.8	178.3	60.2	-190.0	0.87	0.45	-35.91
	5,602.0	1.20	186.80	5,593.8	178.6	59.3	-190.2	0.31	-0.23	-9.77
	5,644.0	1.60	193.50	5,635.8	178.9	58.3	-190.4	1.03	0.95	15.95
	5,688.0	1.90	180.70	5,679.8	179.3	56.9	-190.5	1.12	0.68	-29.09



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well 10-2-4-1W
TVD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
5,732.0	2.20	177.90	5,723.7	179.5	55.4	-190.5	0.72	0.68	-6.36
5,776.0	1.90	171.60	5,767.7	179.6	53.8	-190.4	0.85	-0.68	-14.32
5,820.0	1.80	175.10	5,811.7	179.7	52.4	-190.2	0.34	-0.23	7.95
5,862.0	1.00	151.70	5,853.7	179.6	51.4	-190.0	2.30	-1.90	-55.71
5,905.0	1.20	163.90	5,896.7	179.4	50.7	-189.7	0.71	0.47	28.37
5,948.0	1.60	170.00	5,939.6	179.4	49.6	-189.4	0.99	0.93	14.19
5,992.0	2.10	178.90	5,983.6	179.5	48.2	-189.3	1.31	1.14	20.23
6,034.0	2.30	166.20	6,025.6	179.5	46.6	-189.1	1.25	0.48	-30.24
6,078.0	2.00	168.30	6,069.6	179.4	45.0	-188.7	0.70	-0.68	4.77
6,122.0	1.40	171.20	6,113.5	179.3	43.7	-188.5	1.38	-1.36	6.59
6,165.0	0.80	157.80	6,156.5	179.3	42.9	-188.3	1.51	-1.40	-31.16
6,209.0	1.00	173.70	6,200.5	179.2	42.3	-188.1	0.72	0.45	36.14
6,252.0	1.50	178.40	6,243.5	179.3	41.3	-188.1	1.19	1.16	10.93
6,296.0	2.00	170.10	6,287.5	179.4	40.0	-187.9	1.27	1.14	-18.86
6,340.0	1.70	171.30	6,331.5	179.4	38.6	-187.7	0.69	-0.68	2.73
6,383.0	1.70	177.00	6,374.5	179.4	37.3	-187.6	0.39	0.00	13.26
6,427.0	2.00	176.60	6,418.4	179.6	35.9	-187.5	0.68	0.68	-0.91
6,471.0	2.20	177.10	6,462.4	179.7	34.3	-187.4	0.46	0.45	1.14
6,515.0	2.60	167.00	6,506.4	179.8	32.5	-187.1	1.32	0.91	-22.95
6,557.0	2.60	152.20	6,548.3	179.4	30.7	-186.5	1.59	0.00	-35.24
6,601.0	2.40	159.10	6,592.3	178.9	29.0	-185.7	0.82	-0.45	15.68
6,645.0	2.60	155.60	6,636.2	178.4	27.2	-184.9	0.57	0.45	-7.95
6,689.0	2.50	159.50	6,680.2	178.0	25.4	-184.2	0.46	-0.23	8.86
6,732.0	2.70	154.40	6,723.1	177.5	23.6	-183.4	0.71	0.47	-11.86
6,775.0	4.00	165.10	6,766.1	177.0	21.2	-182.6	3.34	3.02	24.88
6,819.0	4.10	162.80	6,810.0	176.7	18.3	-181.7	0.43	0.23	-5.23
6,863.0	2.90	160.20	6,853.9	176.2	15.7	-180.9	2.75	-2.73	-5.91



Payzone Directional

End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well 10-2-4-1W
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	6,905.0	1.90	144.00	6,895.8	175.7	14.1	-180.1	2.85	-2.38	-38.57
	6,949.0	1.70	140.30	6,939.8	175.0	13.1	-179.3	0.53	-0.45	-8.41
	6,993.0	2.00	129.60	6,983.8	174.2	12.1	-178.3	1.04	0.68	-24.32
	7,037.0	1.60	137.90	7,027.8	173.4	11.1	-177.3	1.08	-0.91	18.86
	7,081.0	1.70	131.10	7,071.8	172.6	10.2	-176.4	0.50	0.23	-15.45
	7,124.0	1.50	138.70	7,114.7	171.9	9.4	-175.5	0.68	-0.47	17.67
	7,168.0	1.10	145.30	7,158.7	171.4	8.6	-174.9	0.97	-0.91	15.00
	7,212.0	1.30	155.30	7,202.7	171.1	7.8	-174.5	0.66	0.45	22.73
	7,256.0	1.30	146.90	7,246.7	170.8	6.9	-174.0	0.43	0.00	-19.09
	7,299.0	1.10	165.30	7,289.7	170.5	6.1	-173.6	1.00	-0.47	42.79
	7,343.0	1.50	173.80	7,333.7	170.5	5.2	-173.4	1.01	0.91	19.32
	7,386.0	1.70	178.30	7,376.7	170.6	4.0	-173.4	0.55	0.47	10.47
	7,430.0	1.70	177.50	7,420.7	170.8	2.6	-173.3	0.05	0.00	-1.82
	7,474.0	1.60	178.10	7,464.6	170.9	1.4	-173.3	0.23	-0.23	1.36
	7,517.0	1.60	179.80	7,507.6	171.1	0.2	-173.2	0.11	0.00	3.95
	7,561.0	1.90	191.80	7,551.6	171.4	-1.1	-173.4	1.07	0.68	27.27
	7,605.0	1.90	194.80	7,595.6	172.0	-2.6	-173.7	0.23	0.00	6.82
	7,649.0	1.90	192.10	7,639.5	172.5	-4.0	-174.1	0.20	0.00	-6.14
	7,691.0	1.90	191.50	7,681.5	173.0	-5.3	-174.3	0.05	0.00	-1.43
	7,734.0	1.90	190.80	7,724.5	173.5	-6.7	-174.6	0.05	0.00	-1.63
	7,777.0	2.00	191.10	7,767.5	174.0	-8.2	-174.9	0.23	0.23	0.70
	7,820.0	2.40	190.20	7,810.4	174.6	-9.8	-175.2	0.93	0.93	-2.09
	7,862.0	2.20	185.00	7,852.4	175.1	-11.5	-175.4	0.69	-0.48	-12.38
	7,906.0	2.20	185.40	7,896.4	175.5	-13.2	-175.6	0.03	0.00	0.91
	7,950.0	2.10	186.30	7,940.3	175.9	-14.8	-175.7	0.24	-0.23	2.05
	7,994.0	2.30	190.40	7,984.3	176.4	-16.5	-176.0	0.58	0.45	9.32
	8,037.0	2.10	186.90	8,027.3	176.9	-18.1	-176.2	0.56	-0.47	-8.14



Payzone Directional
End of Well Report



Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 2 T4S, R1W
Well: 10-2-4-1W
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well 10-2-4-1W
MD Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
North Reference: 10-2-4-1W @ 5050.0usft (CAPSTAR 329)
Survey Calculation Method: True
Database: Minimum Curvature
EDM 5000.1 Single User Db



Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	8,080.0	1.90	196.70	8,070.3	177.4	-19.6	-176.5	0.92	-0.47	22.79
	8,123.0	1.90	199.00	8,113.2	178.1	-20.9	-177.0	0.18	0.00	5.35
	8,167.0	2.00	189.50	8,157.2	178.7	-22.4	-177.3	0.77	0.23	-21.59
	8,211.0	2.20	190.10	8,201.2	179.2	-24.0	-177.6	0.46	0.45	1.36
	8,254.0	2.10	191.50	8,244.1	179.7	-25.5	-177.9	0.26	-0.23	3.26
	8,270.0	2.10	192.10	8,260.1	179.9	-26.1	-178.0	0.14	0.00	3.75
	8,330.0	2.10	194.30	8,320.1	180.8	-28.3	-178.5	0.13	0.00	3.67

Checked By: _____ Approved By: _____ Date: _____



Project: USGS Myton SW (UT)
 Site: SECTION 2 T4S, R1W
 Well: 10-2-4-1W
 Design: Actual

Azimuths to True North
 Magnetic North: 10.93°
 Magnetic Field
 Strength: 52072.8snT
 Dip Angle: 65.84°
 Date: 4/11/2014
 Model: GRF2010



Design: Actual (10-2-4-1W/Wellbore #1)

Created By: *Matthew Linton* Date: 8:24, April 29 2014

THIS SURVEY IS CORRECT TO THE BEST OF
 MY KNOWLEDGE AND IS SUPPORTED
 BY ACTUAL FIELD DATA



Summary Rig Activity

Well Name: Thayer 10-2-4-1W

Sundry Number: 51809 API Well Number: 43047542520000

Job Category		Job Start Date		Job End Date	
Daily Operations					
Report Start Date	Report End Date	24hr Activity Summary			
5/8/2014	5/9/2014	Install BOPs & flowback lines. Ran CBL under 0 psi. Pressure test well control equipment. Perforate 1st stage.			
Start Time	End Time	Comment			
06:00	08:00	NU Cameron 10K 5-1/4" wellhead isolation tool. NU Weatherford 10K frac valve & 10K blind rams.			
Start Time	End Time	Comment			
08:00	10:00	Run CBL from 8210' to surface under 0 psi. TOC @ surface.			
Start Time	End Time	Comment			
10:00	12:00	Pressure test csg to 6900 psi for 30 min. Pressure test well control stack & flowback lines to 10000 psi for 10 min. Low tests of 250-300 psi for 5 min.			
Start Time	End Time	Comment			
12:00	13:00	Perforate stage 1.			
Start Time	End Time	Comment			
13:00	00:00	SDFN			
Report Start Date	Report End Date	24hr Activity Summary			
5/9/2014	5/10/2014	Frac 6 stages & flow back.			
Start Time	End Time	Comment			
00:00	06:30	SDFN			
Start Time	End Time	Comment			
06:30	07:00	Held safety meeting w/ Halliburton frac crew & Extreme WL crew			
Start Time	End Time	Comment			
07:00	08:00	Frac stage 1			
Start Time	End Time	Comment			
08:00	09:00	Set CFTP & perforate stage 2.			
Start Time	End Time	Comment			
09:00	09:30	Frac stage 2			
Start Time	End Time	Comment			
09:30	09:50	Lost X-link, flush well bore. Shut down to fix fluid.			
Start Time	End Time	Comment			
09:50	10:20	Continue frac stage 2			
Start Time	End Time	Comment			
10:20	11:15	Set CFTP & perforate stage 3.			
Start Time	End Time	Comment			
11:15	12:00	Frac stage 3			
Start Time	End Time	Comment			
12:00	12:51	Set CFTP & perforate stage 4			
Start Time	End Time	Comment			
12:51	13:45	Frac stage 4			
Start Time	End Time	Comment			
13:45	14:30	Set CFTP & perforate stage 5			
Start Time	End Time	Comment			
14:30	15:00	Frac stage 5			
Start Time	End Time	Comment			
15:00	15:40	Set CFTP & perforate stage 6			
Start Time	End Time	Comment			
15:40	16:20	Frac stage 6			
Start Time	End Time	Comment			
16:20	17:00	RD frac equipment			
Start Time	End Time	Comment			
17:00	00:00	Open well for flowback @ approx 50 BPH			

NEWFIELD



Summary Rig Activity

Well Name: Thayer 10-2-4-1W

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary	Set Kill plugs.	MIRUSU.	NU & test BOPs.	PU tbgs.
5/12/2014	5/13/2014					
Start Time	00:00	End Time			06:00	Comment SDFN
Start Time	06:00	End Time			07:00	Comment Crew travel & JSA
Start Time	07:00	End Time			07:30	Comment WAIT FOR WIRELINE TO FINISH RIGGING DOWN
Start Time	07:30	End Time			08:00	Comment USE WINCH TRUCK TO N/D TOP SET OF 10K BLIND RAMS FROM FRAC STACK
Start Time	08:00	End Time			08:30	Comment SPOT RIG IN - RIG UP
Start Time	08:30	End Time			09:30	Comment WELL STARTED TO GAS AND BLOW OIL OVER HCR VALVE - N/U 10K BLIND RAM TO CONTROL BLEED OFF
Start Time	09:30	End Time			11:30	Comment BLEED WELL OFF - N/D FRAC STACK - N/U 5K BLIND RAMS - STILL WAITING FOR DOUBLE PIPE RAMS
Start Time	11:30	End Time			12:00	Comment N/U DOUBLE PIPE RAMS
Start Time	12:00	End Time			15:00	Comment PRESSURE TEST BOPS - WHILE WAITING ON PRESSURE TEST - R/U WORKFLOOR - CHANGE OVER BLOCKS FOR TBG - R/U PUMP AND HARDLINE - PREP, DRIFT AND TALLY TBG
Start Time	15:00	End Time			18:30	Comment M/U NEW 4 3/4" CHOMP MILL ONTO NEW POBS, 1 JT, XN NIPPLE W/ PUMP THRU PLUG INSTALLED, 1 JT, X NIPPLE 160 JTS - EOT @ 5248'
Start Time	18:30	End Time			19:30	Comment CATCH CIRCULATION - CIRCULATE OIL AND GAS FROM WELLBORE W/ 110 BBLs 4% KCL
Start Time	19:30	End Time			20:30	Comment Crew travel
Start Time	20:30	End Time			00:00	Comment SDFN
Report Start Date	Report End Date	24hr Activity Summary	Drill out both kill plugs & 2 CFTPs.			
5/13/2014	5/14/2014					
Start Time	00:00	End Time			06:00	Comment SDFN
Start Time	06:00	End Time			07:00	Comment Crew travel
Start Time	07:00	End Time			08:00	Comment SICP 0 PSI - SITP 0 PSI - OPEN WELL - RIH W/ 8 JTS - TAG 1ST KILL PLUG @ 5470' - R/U RBS POWER SWIVEL - CATCH CIRCULATION
Start Time	08:00	End Time			09:30	Comment DRILL KILL PLUG - 15 MINUTES - TAG 2ND KILL PLUG @ 5480' - DRILL 2ND KILL PLUG - 30 MINUTES ON PLUG - FLOWED WELL BACK @ 1 1/2 BPM @ 1000 PSI FOR 30 MINUTES - TRIED TO BLEED TBG OFF - PUMP THRU PLUG WOULDN'T SEAT - WASHINGTON RUBBER STARTED TO LEAK
Start Time	09:30	End Time			14:00	Comment PUMP 60 BBLs CLEAN 4% KCL DOWN TBG - TRIED TO BLEED TBG OFF AGAIN - PLUG STILL WOULDN'T SEAT - CONT. TO FLOW CSG @ 1 1/2 BPM @ 1000 PSI - MADE SEVERAL MORE ATTEMPTS TO SEAT PUMP THRU PLUG - AFTER SEATING PLUG REPLACED WASHINGTON RUBBER

NEWFIELD



Well Name: Thayer 10-2-4-1W

Summary Rig Activity

Start Time	14:00	End Time	18:30	Comment
				RIH W/ 12 JTS - TAG 1ST FRAC PLUG @ 5880' - UNHANG SWIVEL - DRILL PLUG - 25 MINUTES ON PLUG - HANG BACK SWIVEL - RIH W/ TBG TAG PLUG @ 6540' - DRILL PLUG - 25 MINUTES ON PLUG - CIRCULATE WELL CLEAN W/ 130 BBLs 4% KCL - START WELL FLOWING TO PRODUCTION TANKS ON 9% CHOKE
Start Time	18:30	End Time	19:30	Comment
				Crew travel
Start Time	19:30	End Time	00:00	Comment
				Flow well to production tanks over night
Report Start Date	5/14/2014	Report End Date	5/15/2014	24hr Activity Summary
Start Time	00:00	End Time	06:00	Drill out remaining 3 plugs & clean out to PBTD. LD tbg to get above perfs. Leave flowing to tanks over night.
				Comment
Start Time	06:00	End Time	07:00	Comment
				Flow well up csg to production tanks.
Start Time	07:00	End Time	08:00	Comment
				CREW TRAVEL AND JSP MEETING
Start Time	08:00	End Time	14:30	Comment
				SITP 500 PSI - CSG FLOWING ON 10 CHOKE @ 900 PSI - PUMP 30 BBLs DOWN TBG - BLEED TBG OFF - HANG BACK POWER SWIVEL
Start Time	14:30	End Time	15:30	Comment
				RIH - TAG 5TH PLUG @ 7480' - DRILL PLUG - 30 MINUTES ON PLUG - CIRCULATE FOR 10 MINUTES - BLEED TBG OFF - RIH TAG 6TH PLUG @ 7660' - DRILL PLUG - 30 MINUTES ON PLUG - CIRCULATE 10 MINUTES - BLEED TBG OFF - RIH TO 7TH PLUG @ 7880' - DRILL PLUG - 30 MINUTES ON PLUG - CIRCULATE 10 MINUTES - BLEED OFF TBG - RIH TAG FILL @ 8020' - CLEAN OUT 250' OF SAND TO PBTD @ 8274' - CIRCULATE WELL CLEAN W/ 180 BBLs 4% KCL - DROPPED 10 POLYMER STICKS WHILE CLEANING OUT SAND - WHILE DRILLING PLUGS PUMP RATES WERE 2 BPM AND RETURN RATES WERE 3 - 3 1/2 BPM - WHILE BETWEEN PLUGS FLOW RATES WERE KEPT @ +/- 1 1/2 BPM
Start Time	15:30	End Time	16:30	Comment
				FLOW WELL BACK @ 1 1/2 BPM FOR 20 MINUTES - SHUT WELL IN - ISICP 550 PSI - 15 MINUTE SICP 680 PSI - WELL BORE FLUID WEIGHT 8.5 PPG - KILL FLUID WEIGHT NEEDS TO BE 10.2 PPG
Start Time	16:30	End Time	19:00	Comment
				L/D 86 JTS - 92 JTS TOTAL OUT - EOT @ 5513'
Start Time	19:00	End Time	20:00	Comment
				LUBRICATE HANGER IN WELL - LAND TBG - BLEED OFF BOP STACK - R/D WORKFLOOR - N/D DOUBLE GATE PIPE RAMS - N/D SINGLE GATE BLIND RAMS - N/U XMAS TREE - SHUT IN TBG - FLOW CSG ON 9 CHOKE TO PRODUCTION TANKS OVER NIGHT - CSG FLOWING @ 750 PSI
Start Time	20:00	End Time	00:00	Comment
				CREW TRAVEL HOME
Report Start Date	5/15/2014	Report End Date	5/16/2014	24hr Activity Summary
Start Time	00:00	End Time	06:00	Flow well up csg to production tanks.
				Comment
Start Time	06:00	End Time	07:00	Comment
				Well was flowing up csg to production tanks.
Start Time	07:00	End Time	08:00	Comment
				Crew travel
				Rig down

NEWFIELD



Summary Rig Activity

Well Name: Thayer 10-2-4-1W

Start Time	08:00	End Time	10:30	Comment R/U DELSCO - RIH TO FISH PUMP THRU TBG PLUG - LATCH ONTO PLUG BUT DELSCO COULDN'T PULL PLUG - PUMP ON TBG TO EQUILIZE WELL PRESSURE
Start Time	10:30	End Time	12:00	Comment PLUMB TBG FLOWLINE TO FLOWLINE BUNDLE - PRESSURE TEST FLOWLINE TO 800 PSI - GOOD TEST - START TBG TO FLOW ON 9 CHOKE
Start Time	12:00	End Time	15:30	Comment PRESSURE WASH RIG AND EQUIPMENT
Start Time	15:30	End Time	16:30	Comment Crew travel
Start Time	16:30	End Time	00:00	Comment Leave well flowing up tbg to production tanks